

Krebs Engineering, Inc.
2100 Riverhaven Drive, Suite 100
Birmingham, AL 35244
205-987-7411
April 26, 2021

ADDENDUM NO. 4

CONTRACT NO.: 20021

OWNER: Madison Utilities

PROJECT: Quarry Water Treatment Plant Expansion

BID DATE: April 28, 2021

TO: ALL PROSPECTIVE CONTRACTORS AND SUPPLIERS

The changes, modifications, and/or additions covered by and set forth in this Addendum No. 4 shall become part of and be incorporated in the Contract Documents for the above referenced project:

CLARIFICATIONS:

- CL4.1 All the actuators supplied with the filters shall be the same manufacturer as specified.
- CL4.2 Contractors are reminded to revise the Landscaping Allowance to \$50,000 on the proposal form as previously stated in Addendum No. 2.
- CL4.3 The existing sign should be removed and Contractors should include the cost in their price to replace it once the project is completed.
- CL4.4 The entire relocated filtration units shall be warrantied per the Contract Documents.
- CL4.5 The potential gas line relocated noted on Sheet C3-04. Contractors are responsible for investigating the potential conflict and coordinating the relocation. If relocation is required, the Owner will pay the gas company directly for any relocation charges.
- CL4.6 The Owner has a spoil location on Jim Williams Road that can be used by the Contractor is needed. The Contractor shall provide an estimated quantity and coordinate spoil delivery prior to beginning any hauling activities.
- CL4.7 The new Clearwells and Finished Water Pumping Station were designed for soil backfill.
- CL4.8 Based on borings the approximate first 7-feet of soil is select fill material.
- CL4.9 The relocated pump columns are 12-inch. This should be field verified prior to submittals.

SPECIFICATIONS TO BE REVISED BY ADDENDUM:

AD4.1 SECTION 22 05 23 – VALVES

1. Page 22 05 23-4; 2.1 MANUFACTURERS
 - a. Revise B.8 to include: "d. Flowmatic"

AD4.2 SECTION 26 05 00 – BASIC ELECTRICAL MATERIALS AND METHODS

2. Page 26 05 00-5; 3.2 CLEARANCE WITH UTILITIES
 - a. Revise B. and C. to the following: "On many projects the power and telecommunications companies may levy charges due to locations, size or type of services involved. The OWNER shall be responsible for these charges on these project."

DRAWINGS TO BE REVISED BY ADDENDUM:

AD4.3 The minimum required kAIC/WCR rating of the following equipment (originally specified on sheets E1-01 & E1-04) shall be changed from 100kAIC to 85kAIC:

1. MTS-1
2. MTS-2
3. MTS-4
4. MTS-5
5. Finished Water Pump No. 1 VFD
6. Finished Water Pump No. 2 VFD
7. Finished Water Pump No. 3 RVSS
8. Finished Water Pump No. 4 RVSS
9. Backwash Pump No. 1 RVSS
10. Backwash Pump No. 2 RVSS

Krebs Engineering, Inc.

By 

Caleb L. Leach, P.E.
Associate

THIS IS THE LAST PAGE

Attachments to Addendum No. 4 preceding this page:

None

A total of 3 pages or sheets of drawings (including this page) have been included in Addendum No. 4.

General Contractors are requested to return this page as an acknowledgement that you have received this Addendum by e-mail. This will NOT be mailed. A copy of this Addendum may be picked up at the office of the Engineer.

Return to Return to Alabama Graphics Digital Plan Room.

Received By _____

Contractor _____

Date _____